BRUHAT BANGALORE MAHANAGARA PALIKE
DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division
SCHDULE-B

Name of Work:Improvements and Development of NMH Extension in Bagalagunte ward No 14

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures	In Words (Rs)
1	2	3	4	5	6
1	Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface. picking up scarified materials and stacking of old serviceable materials with lead of 100mtr. sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour, HOM of machineries complete as per specifications	Sqm	4226.70	133.56	Rupees One Hundred thirty three & Fifty Six Paise Only
2	Excavation for road, drains and similar works Earthwork excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed. the disposed earth to be leveled neatly after breaking of clods complete as per specifications	Cum	942.48	189.74	Rupees One Hundred Eighty Nine & Seventy Four Paise Only
3	Removing B S Slab drain and Stacking	Sqm	1428.00	104.94	Rupees one hundred Four & Ninety four Paise Only
4	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs. with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour.	Cum	78.54	4443.52	Rupees Four Thousand Four hundred Forty three & Fifty Two Paise Only
			78.54	5421.90	Rupees Five Thousand four hundred twenty one & Ninety Paise
5	Providing laying plain/reinforced cement concrete for Box Drain walls of thickness 10cm to 20cm including centering shuttering for work etc., complete as per approved drawing and design MORTH specification No.1500, 1700, 2200 PCC M20 Grade upto 0.75m height using concrete mixture.including cost of materials, labour, HOM Complete as per specification.	Cum	375.84	7070.20	Rupees Seven Thousand Seventy & Twenty Paise Only
6	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specifications	Ton	30.07	72326.98	Rupees Seventy two Thousand Three hundred twenty Six & Ninty eight Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer

Scanned by CamScanner

ಕಡತದ ಸಂಖ್ಯೆ .....

7	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	860.40	2208.00	Rupees Two thousand two hundred eight only
8	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100·4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	1576.49	69.80	Rupees Sixty Nine & Eighty Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

Scanned by CamScanner